



ድርጅታችን ሞገድ ኢንጅነሪንግ እና ኮንስትራክሽን ሃ/የተወ/የግል/ማህበር በውቅሮ ዋግዋጎች ኤሌክትሪክ ገመድ እና ኬብል ፋብሪካ ፕሮጀክት የሚገኘው የህንፃ እርጥበት ፡መከላከያ የውጭ ፍሳሽ መስመር እና የኮንክሪት መገጣጠም መሙያ ስራዎች ሥራ በግልፅ ጨረታ አወዳድሮ ማሰራት ይፈልጋል።

- የተለቀቀበት ቀን: 9ርቢ ጉንበት 21, 2018 (27 ቀናት)
- መዝገብ ቀን: ጉንበት 25, 2018 8:30 ጥዋት (ተዘጋ)
- የጨረታ ማስከበርያ ዋጋ:2%
- ቦታ:መቐለ
- የጨረታ ደኩመንት ዋጋ:200
- ጨረታ ሚኒስትሮች ቀንና ሰዓት: ጉንበት 26, 2018 9:00 ጥዋት
- ምድብ: [ገዛውቲን ሕንፃ ስራሕቲን/](#)

ግልፅ የጨረታ ማስታወቂያ

ድርጅታችን ሞገድ ኢንጅነሪንግ እና ኮንስትራክሽን ሃ/የተወ/የግል/ማህበር በውቅሮ ዋግዋጎች ኤሌክትሪክ ገመድ እና ኬብል ፋብሪካ ፕሮጀክት የሚገኘው የህንፃ እርጥበት ፡መከላከያ የውጭ ፍሳሽ መስመር እና የኮንክሪት መገጣጠም መሙያ ስራዎች ሥራ በግልፅ ጨረታ አወዳድሮ ማሰራት ይፈልጋል። ስለሆነም ከዚህ በታች የተዘረዘሩት መሰረዳቶችን የሚያሟላ ማህተም ተጨማሪ መወዳደር ይችላል።

01. ተወዳዳሪዎች ሙሉ ስም፣አድራሻ ፣ፊርማ፣ማህተም መኖር አለበት።

02. የታደሰ የ2018 ዓ/ም ግድ ፍቃድ፣ቲን ቁጥር ቫት እና የአቅራቢነት ካርድ ቫት ማቅረብ አለበት። 03.በዘርፉ ፍቃድ ያለው በዋተር ፕራፍ እና ብሲላንት ስራ ልምድ ከሚታወቁ ድርጅቶች ማቅረብ የሚችል

04. ተወዳዳሪዎች የሚያሰጡት ዋጋ ከቫት በፊት መሆን አለበት።

05. የሚሞላው ዋጋ ሲፃፍ(ሲሞላ) ለእይታ ግልፅ መሆን አለበት።

06. ተጨማሪ የሚያቀርቡትን ዋጋ ከነትራንስፖርት ውቅሮ ዋግዋጎች ኤሌክትሪክ ገመድ እና ኬብል ፋብሪካ ፕሮጀክት በራሳቸው ትራንስፖርት የሚያደርሱበት ጨምሮ ይሆናል።

07. የጨረታው ዝርዝር የያዘ ደኩሜንት ከ 20/09/2018 ዓ/ም ጀምሮ ከዋና ቢሮ ሞገድ ኢንጅነሪንግ እና ኮንስትራክሽን ሃ/የተ/የግ/ማሕበር ከፋይናንስ ክፍል በስራ ቀናት ዲያስፖራ አከባቢ አዲሱ ማድያ አጠገብ የሚገኘው ባለ ዘጠኝ ህንፃ ከአንደኛ ፎቅ ቢሮ የማይመለስ 200.00 (ሁለት መቶ ብር) በመፈወስ

08. የጨረታ ማክበርያ (CPO) ካቀረቡት ጠቅላላ ዋጋ 2%(ሁለት ፐርሰንት) በድርጅታችን ሞገድ ኢንጅነሪንግ እና ኮንስትራክሽን ሃ/የተ/የግ/ማህበር ስም ህጋዊነቱ ከተረጋገጠ ፋይናንሻል ተቋሞች (CPO) በፖስታ ታሽጎ መቅረብ አለበት ።

09. የጨረታው ፋይናንሻል ደኩሜንት ኦርጅናል፣የቴክኒካል ደኩሜንት እና የጨረታ ማስከበርያ (CPO) ፣ ፋይናንሻል ደኩሜንት ኮፒ እና ቴክኒካል ደኩሜንት ኮፒ ለየብቻው በአራት ፖስታ (ኢንቨሎፕ) ታሽጎ በፖስታው ተፅፎ (ተለይቶ) ግልፅ አድርጎ ወደ ዋና ቢሮ ሞገድ ኢንጅነሪንግ እና ኮንስትራክሽን ሃ/የተወ/የግል/ማህበር በተዘጋጀ የጨረታ ሳጥን ገቢ የሚደረግበት ከቀን 20/09/2018 ዓ/ም

4:00 ሰዓት ጀምሮ እስከ 25/09/2018 ዓ/ም ከሰዓት 8:30 ያለ ግዜ ይሆናል።

10. ጨረታው በቀን 25/09/2018 ዓ/ም ከሰዓት 8:30 የጨረታ ሳጥን ተዘግቶ በዛው በቀን 9:00 ሰዓት ተጨራች ወይም ህጋዊ ወኪላቸው በተገኙበት በዋና ቢሮ ሞገድ ኢንጅነሪንግ እና ኮንስትራክሽን አንደኛ ፎቅ መሰብሰብያ አደራሽ ይከፈታል። ተጨራች ወይም ህጋዊ ወኪላቸው ባይገኙም ህጋዊነቱ እስከተረጋገጠ በሌሉበት ይከፈታል።

11. በጨረታ የቀረበው ንብረት ጨረታው ካሸነፈበት ቀን ጀምሮ በሰዓት ቀናት _ ውል አሰረው ስራው መጀመር አለበት። ዝ

12. የሚያቀርቡት አቅርቦት በስፔሰሪኬሽን መሰረት መሆን አለበት ካልሆነ ግን ድርጅቱ የማይቀበል መሆኑን ሊታወቅ ይገባል ።

13. ድርጅቱ የተሻለ አማራጭ ካገኘ ጨረታው በከፊል ወይም በሙሉ የመሰረዝ መብቱ የተጠበቀ ነው።

ለበለጠ መረጃ በ 0914302134/0968894162 ይደውሉ።

MOGED ENGINEERING AND COSTRUCTION PLC.
SUBJECT: THERMAL AND MOISTURE PROTECTION, SITE SEWARAGE SYSTEM AND JOINT FILLER WORK

S. No.	Description	Unit Qty.	Rate (Birr)	Amount (Birr)	Remark
1	THERMAL AND MOISTURE PROTECTION Supply and Apply APP modified & with thickness not less than 4mm slated finish Water Proofing Membrane or compatible equivalent material for R.C wall as per the manufacturer's instructions and recommendations as shown on the drawing. The cost shall include cleaning of all dirty and dust materials and all incidental works and details of manufacturer.	M2	227.0		
1.1	The work shall be done on sub specialized contractual base with the supplier of the material which will give material and construction guarantee to the client. The contractor must provide company profile and subject to the consultant engineer final approval.				
2	SITE SEWARAGE SYSTEM Supply, lay, test, commission connect HDPE Pipe/PN-16/(ISO-4422) for waste water drainage with the working pressure of 6 bars, complete with all the necessary accessories. The pipes should be laid on a soil without sharp objects & non granular materials with slope as indicated on the drawing per the detail drawing and subject to the consultant engineer final approval.	ML	55		
2.1	a) Ø200 mm Top perforated HDPE Pipe complete With Non-woven Geotextile fabric.				

MOGED ENGINEERING AND COSTRUCTION PLC.

SUBJECT: THERMAL AND MOISTURE PROTECTION, SITE SEWARAGE SYSTEM AND JOINT FILLER WORK

S. No.	Description	Unit	Qty.	Rate (Birr)	Amount (Birr)	Remark
3	Supply and install a 25 mm thick structural expansion joint system between the Retaining Walls, columns and F.pads comprising a 230 mm depth Styrofoam (non-absorbent compressible filler) and a high- performance polyurethane sealant (Sonolastic or approved equivalent). The installation must include thorough surface preparation to ensure joint faces are clean and dry, the application of the sealant to a minimum thickness of 20mm (or as per manufacturer's specifications) with professional tooling to ensure a watertight bond, and full adherence to the structural detail drawings subject to the consultant engineer final approval.	ML	56			

SUM (BIRR)

VAT (15%)

Total (BIRR)