- በዓል መዚ ሓለዋ ከባብን ለውጢ ነባሪ አየርን ትግራይ ካብዚ ንታሕቲ ዝተጠቐሰ ናይ ኣይሲቲ መሳርሒ ኣቐት ብፕሮፎርማ ምልከታ ኣወዳዲሩ ክዕድግ ስለ ዝደልይ

- ዝወፀሉ መዓልቲ: ዓርቢ ጥቅምቲ 22, 2017 (ልዕሊ 2 ዓመታት)
- ዝዕፀወሉ መዓልቲ: ጥቅምቲ 27, 2017 3:30 ቅ/ሰዓት (ተዓፅዩ)
- ናይ ጨረታ መድሓዚ ዋጋ:
- ቦታ:መቐለ
- ናይ ደኩመንት ዋጋ:
- ጨረታ ዝክፈተሉ መዓልቲን ሰዓትን: ጥቅምቲ 27, 2017 4:00 ቅ/ሰዓት
- መደብ: ኮምፒተርን ተዛመድቲ / ናይ ኮምፒተር ተዛመድቲ አቁሑትን/ ኤሌክትሮኒክስ መሳርሕታትን መለዋወጢን/

ፕሮፎርማ ምል'ከታ ቁፅሪ 02/2017 -

በዓል መዚ ሓለዋ ከባብን ለውጢ ነባሪ አየርን ትግራይ ካብዚ ንታሕቲ ዝተጠቐሰ ናይ ኣይሲቲ መሳርሒ ኣቐት ብፕሮፎርማ ምልከታ ኣወዳዲሩ ክዕድግ ስለ ዝደልይ ብዘርፉ ዝተዋፈርኹም ሕጋዊ ነጋዶ ዝኾንኩም ክትወዳደሩ ይዕድም::

| ዓይነት ንብረት | ስፐስፊኬሽን | መዐቐኔ | በዝሒ | ናይ ሓደ ዋጋ | ድምር ዋጋ |
|---|---|---|---|---|---|
| 1 | Unmanageable switch 24 port | plug and play Rackmountable switch with 24 ports 10/100Mbps:<br>UTP transmission for surveillance up to 100m,cat5/5e/6e and above auto detection of the Ethernet cable type Auto MDI/MDIX for all ports, network cable: 100BASE-TX or 1000BASE-TX flow control support fist Ethernet 200Mbps full Duplex,100Mbps half-duplex 4,8 Gbps switching fabric Dimensions 282x150x44mm | Number | 03 | |
| 2 | Wireless Router | Daul band, 4xGigabit LAN port support Access point mode, wireless 802.11b/g/n 2.4GHz 300Mps and 802.11ac/n/a 5GHz 433mbps, WPA/WPA2-Enterprise(802.1X) Single core CPU,IP and MAC binding, Access Control WAN types :Dynamic IP, Static IP, PPPOE,PPTP, L2TP, QOS by Device, NAT forwarding, DHCP | Number | 02 | |
| 3 | 9U Wall Mounted Rack(Data Cabinet) | Size Standard 9U Depth 449.58mm With cat6 utp patch panel 24 ports, power distribution unit, external Sine 229.1mm H x549.9mm * W x450mm" D And with all its accessories | Number | 02 | |
| 4 | Ethernet Cable | UTP Cable Cat6 | Roll | 02 | |
| 5 | Rj 45 | 8 pin connector<br>Can support upto 100Mbps | package | 05 | |
| 6 | Trunking cable | Able to resist 25KV voltage<br>Low friction and<br>Lightweight, easy to cut, transport, bent and handle | package | 01 | |

© መሰሉ ብህጊ ዝተሓለወ እዩ። 2013 - 2026 Made with love in Mekelle

11. ናይ 2016ዓ/ም ንግዲ ፍቓድ ዘሓደሱ

12. ናይ 2016ዓ/ም መቕረባይነት ዘሓደሱ

13. ቲን ነምበር ዘለዎም

14. ፕሮፎርማ ዝወፀሉ ዕለት 22/02/17 ዓ/ም

15. ፕሮፎርማ ዝዕፀወሉ ዕለት 22/02/2017 ዓ/ም ሰዓት 3.30 ቕድሚ ሰዓት

16. ፕሮፎርማ ዝኸፈሉ ዕለት 27/02/2017 ዓ/ም ሰዓት 4.00 ቕድሚ ሰዓት

17. እዚ ፕሮፎርማ ከም ውዕል ኾይኑ የገልግል

18. ዘይተማልኣ ፕሮፎርማ ውድቂ ይኸውን

19. ሰዓራይ ኣብ ቢሮ ኣምፂዑ ከቕርብ ኣለዎ

20. እቲ ዋጋ ፀኒዑ ዝፀንሓሉ ጊዜ 7' ናይ ስራሕ መዓልቲ ይኸውን ንተወሳኺ ሓበሬታ ናብ ናብ በዓል መዚ ሓለዋ ከባቢን ለዉጢ ነባሪ ኣየርን ቢሮ ዕ/ፋ/ን/ምም/ር ብኣካል ብምምፃእ ምጥያቕ ይከኣል :

© መሰሉ ብህጊ ዝተሓለወ እዩ። 2013 - 2026 Made with love in Mekelle