ቤት ፅሕፈት ግልጋሎት ማይን ፍሳስን ከተማ መቐለ ቤት ፅሕፈትና ኣብ ዝተፈላለየ ከባቢታት መስመር ማይን ዝርገሓን ናይ መብየዳ ስራሕ ብፕሮፎርማ ኣወዳዲሩ ከስርሕ ስለ ዝደለየ

- ዝወፀሉ መዓልቲ: ሶኒ መጋቢት 15, 2017 (ቅድሚ ሓደ ዓመት)
- ዝዕፀወሉ መዓልቲ: መጋቢት 18, 2017 11:00 ቅ/ሰዓት (ተዓፅዩ)
- ናይ ጨረታ መድሓዚ ዋጋ:
- ቦታ:መቐለ
- ናይ ደኩመንት ዋጋ:
- ጨረታ ዝክፈተሉ መዓልቲን ሰዓትን: -18, 1745 6:00 ደ/ሰዓት
- መደብ: ጠቅላላ ስራሕቲ ኣገልግሎት/ ኤሌክትሮ-መካኒክስ ኣቁሑትን ግልጋሎትን/ ሰራሕቲ ሓፂነ መፂን/

ፕሮፎርማ መፍለይ ቁፅሪ 32/2017 ዓ/ም

ቤት ፅሕፈት ግልጋሎት ማይን ፍሳስን ከተማ መቐለ ቤት ፅሕፈትና ኣብ ዝተፈላለየ ከባቢታት መስመር ማይን ዝርገሓን ናይ መብየዳ ስራሕ ብፕሮፎርማ ኣወዳዲሩ ከስርሕ ስለ ዝደለየ ኣብዚ ጨረታ ፕሮፎርማ ትወዳደሩ ትደልዩ ነጋዶ ዝስዕብ ሮቅሓ ክተማልኡ ይግባእ።
- ናይ ዘመኑ ሕጋዊ ዝተሓደሰ ንግዲ ፍቃድ ምቅራብ ዝክዕል ዘይተሓደሰ ንግዲ ፍቓድ

ዘየቅረበ ተወዳዳሪ ተቐባልነት የብሉን (ካብ ውድድር ወፃኢ) ይግበር

- ደረጃ 10ን ልዕሊኡ ብማይ ስራሕቲ(WWC))

- ግብሪ ከፋሊ /TI/ንምኻኑ ማስረጃ ምቅራብ ዝኽእል

- ዘይተማለአ ደኩመንት ተቀባልነት የብሉን

- ናይ ተወዳደርቲ ድርጅት ማሕተምን ፊርማን ይገበር

- እቲ ፕሮፎርማ ከም ውዕሊ ኮይኑ የገልግል ::

Item	Description of the work	Unit	Qty	Unit Price Birr	Total Price Birr	Remark
	INSTALLATION AND WELDING OF HDPE, FITTININGS @ E/GEBRAIL STADUIM AND AKRAM SUB-CITY HAWELTI, HAWZEN ADEBABAY K/WEYANE SUB CITY, GEFIH GEREB TO INDUSTRY PARK SUB CITY A/HAKI (MATERIAL SUPPLY FROM THE CLIENT)					
1	Hawzen Adebabay to Mekelle mah (kedamay weyane sub city)					
1.1	Installation and welding of OD 160mm, L=6M, total length 300m. PE 100, PN10 (material supplied from client point warehouse)	53				

© መሰሉ ብህጊ ዝተሓለወ እዩ። 2013 - 2026 Made with love in Mekelle

Item	Description of the work	Unit	Qty	Unit Price Birr	Total Price Birr	Remark
1.2	Installation all the required fittings, valves and accessories for joint connection flanged tee DN150*150*150=01, flanged gat valve DN150=02, short stap with backing ring OD160=03 diameter.	point	06			
2	TPLF office to stadium Endagebrail church (Hawelti sub city)					
2.1	Installation and welding of OD 315mm,, L=6M, total length 1880m. PE 100, PN10 (material supplied from client warehouse)	point	318			
2.22	Installation all the required fittings, valves and accessories for joint connection flanged tee DN300*200*300=01, flanged gat valve DN200=01, flanged gat valve DN300=01 short stap with backing ring OD315=02 diameter, short stap with backing ring OD225=01 diameter.	point	06			
3	Gefih Gereb to food item market (Adihaki sub city)					
3.1	Installation and welding of OD 160mm,, L=6M, total length 1770m. PE 100, PN10 (material supplied from client warehouse)	point	300			
3.2	Installation all the required fittings, valves and accessories for joint connection flanged reducer DN200-150-01, butt welding elbow OD160=01 short stap with backing ring OD225=01 diameter, short stap | with backing ring OD160=01 diameter,	point	04			
4	Akram- (Hawelti)-Messebo Commercial bank (Ayder sub city)					
4.1	Installation and welding of OD 160mm,, L=6M, total length 1300m. PE 100, PN10 (material supplied from client warehouse)	point	222			
4.2	Installation all the required fittings, valves and accessories for joint connection, short stap with backing ring OD225=02 diameter, Flanged plug DN200	point	03			

PRELIMINARY REQUIREMENTS OF THE SELECTED BIDDERS

1. The bidder should have a license of grade 10 and above of WWC.

2. The bidder should have own/leased, two butt welding machines which can install/weld/ a pipe size of OD315,OD225 & OD160mm. (for own legal owner receipt and for lease legal and updated agreement)

3. The bidder should have own/leased, two diesel generators wit size of 5.5kw and above.

4. The scope of the work includes: -

4.1. All pipes and fitting will be supplied from the client (MWSSO). dumped at maximum

© መሰሉ ብህጊ ዝተሓለወ እዩ። 2013 - 2026 Made with love in Mekelle

length of every 100-meter interval.

4.2. Welding points of pipes properly with standard heating and cooling time.

4.3. Laying pipes properly on the excavated trenches.

4.4. Proper connections of flanged materials as specified on the BOQ.

4.5. The bidder should cover by his own cost for the necessary daily laborers.

5. The bidder should finish the installation work within 60 consecutive days.

6. Payment with hold 10% which is released after water leakage tested.

N.B

➢ ንብረት ትቦን መገጣጠምን ኣብ ውዕጢ ዓቕሚ ቤት ፅሕፈት ኮይኑ ብናይ ባዕሉ ባትቄልዲንግ ማሽንን ጀነሬተርን ምስ ሙሉእ ወፃኢኡ ናይ ተጫራታይ ይኸውን

➢ ፅሬት ዘይብሉ ስራሕ እንተተሰሪሑ ተቐባልነት ዘይብሉ ምኻኑ ነፍልጥ

➢ ክፍሊት ብዝምልከት ድማ ዝምልከቶ ኣካል ብትክክል ምስርሑ ብስተረጋገፀ ብዝበየዶ በዝሒ ተሓሲቡ ብዘቕረቦ ሕቶ ክፍሊ መሰረት ይኸፈል

N.B .እቲ ኣብ ላዕሊ ዝተዘርዘረ መረዳእታ ኮፒ ተገይሩ ተደሓሒዙ ክቀርብ አለዎ

ኣብ ኣየር ዝፀንሓሉ ግዜ ካብ ዕለት 15/7/2017 ዓ.ም ክሳብ 17/7/2017 ዓ/ም

ኣድራሻ

ቤት ፅሕፈት ግልጋሎት ማይ ከተማ መቐለ 03 ቀበሌ ስ.ቁ.0344407335

© መሰሉ ብህጊ ዝተሓለወ እዩ። 2013 - 2026 Made with love in Mekelle