



ቤት ፅሕፈት ግልጋሎት ማይን ፍሳሰን ከተማ መቐለ ቤት ፅሕፈትና ናይ በጀት ዓመት 2017 መድፍኢ ረሳሕ ፈሳሲ ዝተጠራቐመ ስላጅ ምዕራግን ምልዓልን ብፕሮጀርማ ኣወዳዳሩ ከስርሕ ስለ ዝደለየ

- ዝወጹ መዓልቲ: ሰኒ ገንበት 4, 2017 (ቅድሚ 12 ወርሒ)
- ዝዕጸዉ መዓልቲ: ገንበት 7, 2017 11:00 ቅ/ሰዓት (ሓሊፉ)
- ናይ ጨረታ መድሓዚ ዋጋ:
- ቦታ: መቐለ
- ናይ ደኩመንት ዋጋ:
- ጨረታ ዝክፈተሉ መዓልቲን ሰዓትን: -18, 1745 6:00 ደ/ሰዓት
- መደብ: ስራሕቲ ማይ/

ፕሮጀርማ መፍለይ ቁፅሪ 46/2017 ዓ/ም

ቤት ፅሕፈት ግልጋሎት ማይን ፍሳሰን ከተማ መቐለ ቤት ፅሕፈትና ናይ በጀት ዓመት 2017 መድፍኢ ረሳሕ ፈሳሲ ዝተጠራቐመ ስላጅ ምዕራግን ምልዓልን ብፕሮጀርማ ኣወዳዳሩ ከስርሕ ስለ ዝደለየ ኣብዚ ጨረታ ፕሮጀርማ ትወዳደሩ ትደልዩ ነጋዶ ዝስዕብ ርቅሓ ክተማልኡ ይግባእ።

- ናይ ዘመኑ ሕጋዊ ዝተሓደሰ ንግዲ ፍቓድ ምቕራብ ዝክዕል ዘይተሓደሰ ንግዲ ፍቓድ ዘየቅረበ ተወዳዳሪ ተቐባልነት የብሉን (ካብ ውድድር ወፃኢ) ይግበር
- ደረጃ 10ን ልዕሊኡ ቢሲ ወይ ጂሲ (gread 10 & Above of BC or GC)
- ግብሪ ከፋሊ /TIN/ንምኻኑ ማስረጃ ምቕራብ ዝኽእል
- ዘይተማለኦ ደኩመንት ተቐባልነት የብሉን
- ናይ ተወዳደርቲ ድርጅት ማሕተምን ፊርማን ይገበር
- እቲ ፕሮጀርማ ከም ውዕሊ ኮይኑ የገልግል ::

BOQ:-1 DRING BED SLUDGE CLEARANCE AND AT AYDER SUB CITY, TABIA MARIAM DHAN

Item Description	Unit Qty	U/Price Birr	T/Price Birr	Remark
1.1 Clear off the site to remove the top soil to an average depth of 20cm including cutting of trees, garbeages and bushes and Cart away the surplus materials to a distance not exceeding 500-700 m (nstructed by the engineer)	m2	4250		
1.2 Excavation and collection of fecal sludge in lagoon foundation to a depth of 40cm from reducing level.	m3	1700		

Item Description	Unit	Qty	U/Price Birr	T/Price Birr	Remark
1.3 Excavation of simple lagoon sludge collector to an area of 12m*10m and debth of 1m at agiven site as instructed by the erngineer.	m3	120			
1.4 Cart away and accumulate the excavated sludge material from the site and Cart away the surplus materials to a distance not exceeding 500-700 m (instructed by the engineer)	m3	1820			
TOTAL-1					
VAT.15%					
Grand Total cost Inculding Vat					

PRELIMINARY REQUIREMENTS OF THE SELECTED BIDDERS

1. The bidder should have a licence of gread 10 and above of BC or GC.
2. The bidder should have own/leased, two dump trucks, one loader above 160HP and excavatpor

(optional).
3. The scope of the work includes: -
 - 3.1. Properly excavating, collecting and catr away the sludge, bushes and trees.
 - 3.2. Any transport and required fuels should be cover by the contractor.
 - 3.3. The bidder should cover by his own cost for the necessary daily laborers.
4. The bidder should finish the installation work with in 10 conscetive days,
5. Payment with hold 10% which is released after the excavated and Collected sludges checked

N.B ናይ ዘመኑ ዝተሓደሰ ንግዲ ፍቓድ ዘየቅረብ ካብ ውድድር ወፃኢ -

ኣብ ኣየር ዝፀንገሉ ግዜ ካብ ዕለት 4/9/2017 ዓ.ም ክሳብ 6/9/2017ዓ/ም

እቲ ፍቓድ ኮፒ ተደሓሒዞ ክቀርብ ኣለዎ

ኣድራሻ

ቤት ፅሕፈት ግልጋሎት ማይ ከተማ መቐለ 03 ቀበሌ ስ.ቁ 0344407335