ኢንተርፕራይዝ መፅናዕቲ፣ዲዛይንን ቁፅፅርን ስራሕቲ ማይ ትግራይ ካብዚ ንታሕቲ ዘሎ ናይ ህንፃ መሳርሒ ኣቑሑት ብግልፂ ጨረታ ኣወዳዲሩ ክዕድግ ስለዝደለየ

- ዝወፀሉ መዓልቲ: ቀዳም ጥቅምቲ 29, 2018 (ቅድሚ 12 ወርሒ)
- ዝዕፀወሉ መዓልቲ: ሕዳር 13, 2018 4:00 ቅ/ሰዓት (ተዓፅዩ)
- ናይ ጨረታ መድሓዚ ዋጋ:3000
- ቦታ:መቐለ
- ናይ ደኩመንት ዋጋ:200
- ጨረታ ዝክፈተሉ መዓልቲን ሰዓትን: ሕዳር 13, 2018 4:30 ቅ/ሰዓት
- መደብ: ኮንስትራክሽን ማሽነሪን ኣቑሑትን/ ናይ ምህንድስና ኣቑሑት/

ቑፅሪ/Ref no ኢመዲቁ፦ 0331/15/18

ዕለት/Date: 29/02/2018

ግልፂ ጨረታ

ኢንተርፕራይዝ መፅናዕቲ፣ዲዛይንን ቁፅፅርን ስራሕቲ ማይ ትግራይ ካብዚ ንታሕቲ ዘሎ ናይ ህንፃ መሳርሒ ኣቑሑት ብግልፂ ጨረታ ኣወዳዲሩ ክዕድግ ስለዝደለየ ካብዚ ቐፂሉ ዘሎ መስፈርቲ እተማልኡ ተወዳደርቲ ዘይምለስ ብር 200.00 (ክልተ ሚኢቲ) ብምኽፋል ትካል ዘዳለዎ ሰነድ ጨረታ ወሲድኩም ንክትወዳደሩ ንዕድም::

1. ናይ 2017 ዓ/ም ዝተሓደሰ ሕጋዊ ንግዲ ፍቓድ ኮፒ ክተታሓሕዙ ትክእሉ።

2. ናይ መቕረባይ ምዝገባ ሰርትፊኬትን II ቑፅሪ ዝሓዘ ኮፒ ክተታሓሕዙ ትኽእሉ።

3. ቫት ተመዝጋቢ ተኾይኖም ናይ ቫት ሰርትፊኬት ኮፒን ዘቕርብዎ መወዳደሪ ዋጋ ቫት ዝሓወሰ ክኸውን ኣለዎ።

4. ናይ ወርሒ ነሓሰ ቫት ዲክለር ዝገበርኩምሉ ኮፒ ክተቕርቡ እትኽእሉ።

5. ጨረታ መኽበሪ ብ C.P.O.ወይ ብጥረ ገንዘብ 3,000.00 (ሰለስተ ሽሕ) ብር ከትሕዙ ዝኽእሉ።

6. ዝተኣዘዘ ንብረት አሸናፊ ኾይኖም እንትርከቡ ውዕሊ ኣሲሮም ንብረት ኣብ 15ተ መዓልቲ ብውዕሊ መሰረት የረክቡ።

7. ጨረታ አብ አየር ዝፀንሓሉ ጊዜ ካብ ዕለት 29/02/2018 ክሳብ 13/03/2018 ዓ/ም ኮይኑ በቲ ዕለት ልክዕ ስዓት 4:00 ተዓሸጉ ስዓት 4:30 ይኽፈት ።

8. ትካልና ካልእ ዝሓሸ መማረፂ እንተረኺቡ ብሙሉእ ይኹን ብኽፋል ናይ ምስራዝ መሰሉ ዝተሓለወ እዩ::

➢ ንተወሳኺ ሓበሬታ ብስ/ቁ 0914-752718 ወይም ብኣካል ብምምፃእ ዓዲ ሓ ጥቓ ገነት መዕደሊ ነዳዲ ኣብ ዝርከብ ትካልና ምርካብ ይከኣል እዩ።

© መሰሉ ብህጊ ዝተሓለወ እዩ። 2013 - 2026 Made with love in Mekelle

ዝርዝር ንብረት

ተ/ቁ	ዓይነት ንብረት	መዕቀኒ	በዝሒ	ነ/ዋጋ ብር ሳ	ጠ/ዋጋ ብር ሳ	መብርሂ
1	HAND RAIL					
1.1	Hand rail for Stair case & guard rail for balcony using CHS /Circular Hollow section galvanized steel tube) for .post.pole & other work price including 2 coats antirust paint & with all necessary accessories.(material quality approved by the engineer)					
	a). CHS diameter 50mm, thickness 2.0 mm	Berga/Pes	10			
	b). CHS diameter 38mm, thickness 1.5 mm	Berga/Pes	19			
	c). CHS diameter 22mm, thickness 1.25mm	Berga/Pes	59			
2	FLOORING WORK					
2.1	3cm thick Granite window sill with 25cm width	ml	6			
2.2	3cm thick Granite for Tread and 2cm thick Riser (color & material quality approved by the engineer). Note for Tread size of Granite (1.45mx0.34m-8pcs, 1.48x0.3-4m 2pcs and Riser (1.48mx0.14 2pcs)	M2	5.4			
2.3	Granite for Door Sill (size 90*25cm-10pcs and 150*25cm-4pcs). (color & material quality approved by the engineer)	M2	4			
2.4	Ceramic tile Floor Finishing works (30x30x1.5cm) for Toilet. (color & material quality approved by the engineer)	M2	147			Made in Ethiopia
2.5	Use 6 mm thick ceramic tiles for wall with cement sand mortar (1:2) ratio to toilet,shawor and hand wash basines & indicated surface (M color & material quality approved by the engineer)	M2	256			
	3. BLOCK WORK					
3.1	20 20 40cm thick hollow concrete block wall bedded in cement sand mortar 1:3 ratio (class of H.C.B should be class"B")	M2	4.8			
	4. Material Supply					
4.1	Sand (1 Truck Sino-16m3) and material quality approved by the engineer.	M2	32			
4.2	Gravel (Aggregate 00) and material quality approved by the engineer.	M2	16			

© መሰሉ ብህጊ ዝተሓለወ እዩ። 2013 - 2026 Made with love in Mekelle